

移植工事

工作センター西側

記号	樹木名	規格			本数	幹径	根径	根深	バフ体積	根体積	根長	支柱	支給苗畑	備考
		H	C	W										
☆	アカマツ	200~			173	73	34	1.00	173.00	0.01	1.73	八ヶ岳(竹)	第2苗圃	林外移植
◎	シラカシ	15~19			10	79	37	1.25	12.50	0.02	0.25	二脚鳥居	光ノア線東側	
①	ソメイヨシノ	25~29			6	154	78	6.00	36.00	0.05	0.25	十字鳥居	第2苗圃	
◎	キンモクセイ	15~19			1	79	37	1.25	1.25	0.02	0.25	八ヶ岳(竹)		
	"	15~17			2	86	41	1.75	3.50	0.02	0.25	"		
	"	15~19			1	92	45	2.00	2.00	0.03	0.25	"		
	"	20~24			1	104	51	3.00	3.00	0.03	0.25	"		
④	ネズコ	9~11			4	73	34	1.00	4.00	0.01	0.25	"		
	"	12~16			19	79	37	1.25	23.25	0.02	0.25	"		
	"	15~17			3	86	41	1.75	5.25	0.02	0.25	"		
	"	18~19			2	92	45	2.00	4.00	0.03	0.25	"		
⑩	トチノキ	12~16			9	79	37	1.25	11.25	0.02	0.25	二脚鳥居		
	"	15~17			8	86	41	1.75	14.00	0.02	0.25	"		
	"	18~19			3	92	45	2.00	6.00	0.03	0.25	"		
②	カツラ	12~16			2	79	37	1.25	2.50	0.02	0.25	"		
	"	15~17			3	86	41	1.75	5.25	0.02	0.25	"		
	"	18~19			6	92	45	2.00	12.00	0.03	0.25	"		
⑤	ケヤキ	15~19			5	79	37	1.25	6.25	0.02	0.25	"	第2苗圃、ベツ西	
	"	18~19			3	86	41	1.75	5.25	0.02	0.25	"	"	
◎	クマノミズキ	12~16			1	79	37	1.25	1.25	0.02	0.25	"	第2苗圃、豊永通り東側	
	"	15~17			3	86	41	1.75	5.25	0.02	0.25	"	"	
	"	18~19			3	92	45	2.00	6.00	0.03	0.25	"	"	
	"	20~24			7	104	51	3.00	21.00	0.03	0.25	"	"	
	"	25~29			6	118	58	4.50	27.00	0.03	0.25	"	"	
④	ホソエカエデ	9~11			3	73	34	1.00	3.00	0.01	0.25	"	第2苗圃	

	"	15~17			1	79	37	1.25	1.25	0.02	0.25	"	"	
	"	18~19			1	86	41	1.75	1.75	0.02	0.25	"	"	
◎	シオシ	12~16			6	79	37	1.25	7.50	0.02	0.25	"	ベツ西	
	"	15~17			5	86	41	1.75	8.75	0.02	0.25	"	"	
	"	18~19			1	92	45	2.00	2.00	0.03	0.25	"	"	
◎	フサヅクラ	12~16			8	79	37	1.25	10.00	0.02	0.25	"	第2苗圃	
	"	15~17			1	86	41	1.75	1.75	0.02	0.25	"	"	
◎	イロハモミジ	15~17			5	86	41	1.75	8.75	0.02	0.25	"	"	
①	イヌシデ	12~16			1	79	37	1.25	1.25	0.02	0.25	"	"	
	"	15~17			7	86	41	1.75	12.25	0.02	0.25	"	"	
	"	18~19			4	92	45	2.00	8.00	0.03	0.25	"	"	
◎	ブナ	12~16			13	79	37	1.25	16.25	0.02	0.25	八ヶ岳(竹)	第2苗圃	
◎	クマシデ	15~17			12	86	41	1.75	21.00	0.02	0.25	二脚鳥居	第2苗圃	
⊠	アセビ	100~149			12	53	34	0.50	6.00	0.005	0.25	添支柱(竹)	サブロー建設	
☆	アカマツ	200~			57	73	34	1.00	57.00	0.01	0.25	八ヶ岳(竹)	第2苗圃	林外移植
◎	シラカシ	12~16			6	79	37	1.25	7.50	0.02	0.25	二脚鳥居	光ノア線東側	
◎	ソメイヨシノ	25~29			3	154	78	6.00	18.00	0.05	0.25	十字鳥居	第2苗圃	
◎	キンモクセイ	12~16			3	79	37	1.25	3.75	0.02	0.25	八ヶ岳(竹)		
合計					430				587.00		6.75			

新規工事

工作センター西側

記号	樹木名	規格			本数	幹径	根径	根深	バフ体積	根体積	根長	支柱	支給苗畑	備考
		H	C	W										
○	シラカシ	2.5	0.1	0.6	30	73	34	1.00	30.00	0.01	0.20	八ヶ岳(竹)	科想購入	林外移植
◎	メブツバキ	2.5	0.8	2.0	73	34	1.00	20.00	0.01	0.20	"	"		
△	ヒノキ	2.5	0.5	2.5	73	34	1.00	25.00	0.01	0.20	"	"		
●	イヌツゲ	1.5	0.6	1.6	65	40	1.00	16.00	0.01	0.16	"	"		
▽	ヒイラギ	1.5	0.4	2.2	65	40	1.00	22.00	0.01	0.22	"	"		
⊠	ヒサカキ	1.5	0.6	1.8	65	40	1.00	18.00	0.01	0.18	"	"		
○	シラカシ	2.5	0.1	0.6	368	73	34	1.00	368.00	0.01	3.08	"	"	林外移植
◎	メブツバキ	2.5	0.8	1.5	73	34	1.00	15.00	0.01	0.15	"	"		
△	ヒノキ	2.5	0.5	1.8	73	34	1.00	18.00	0.01	1.83	"	"		
□	スタジイ	2.5	0.5	2.0	73	34	1.00	20.00	0.01	0.20	"	"		
○	クワガネモチ	2.0	0.6	2.0	73	34	1.00	20.00	0.01	0.20	"	"		
⊗	ウバメガシ	2.0	0.6	2.0	73	34	1.00	20.00	0.01	0.20	"	"		
①	カクレミノ	2.5	0.7	1.2	73	34	1.00	12.00	0.01	0.12	"	"		
合計									947.00		9.47			

八ヶ岳支柱取替工事

樹木名	本数	規格	備考
アカマツ	108		入ヶ岳(支)
合計	108		

支柱: CCA加工 長さ 2.2m  
 規格: CCA加工 長さ 1.2m  
 規格 2.0m